



SCHEDULE OF DOORS & WINDOWS				
TYPE	SIZE	SILL HT.	DESCRIPTION	NOS
D1	3'-6" x 9'-0"	-	CONCRETE FRAMED TIMBER DOOR (2' HIGH CEMENT GRILL AT TOP)	01
D2	3'-0" x 7'-0"	-	CONCRETE FRAMED TIMBER DOOR	05
D3	2'-9" x 7'-0"	-	CONCRETE FRAMED TIMBER DOOR	01
W1	6'-0" x 7'-0"	2'-0"	CONCRETE FRAMED GLAZED WINDOW (2' HIGH CEMENT GRILL AT TOP)	01
W2	6'-0" x 6'-0"	3'-0"	CONCRETE FRAMED GLAZED WINDOW (2' HIGH CEMENT GRILL AT TOP)	04
W3	4'-0" x 6'-0"	3'-0"	CONCRETE FRAMED GLAZED WINDOW (2' HIGH CEMENT GRILL AT TOP)	01
F1	2'-0" x 2'-0"	7'-0"	CEMENT GRILL	01



- IMPORTANT NOTES:**
1. THIS DRAWING REFERS TO A HYPOTHETICAL SITUATION
 2. THE DRAWING SHALL BE USED ONLY AS A GUIDE AND ALTERED TO SUIT A GIVEN LOCATION AND STATUTORY REQUIREMENTS
 3. HOUSE SHALL BE LAID ACCORDING TO THE DIMENSIONS OF THE SELECTED SITE.
 4. EXTERNAL AND INTERNAL WALLS ARE 6" AND 4" THICK CEMENT BLOCK WORK RESPECTIVELY

FLOOR AREA - 924 SQ.FT.
 STAGE 01 - 632 SQ.FT.
 (APPROX. ESTIMATION FOR MATERIAL - Rs.Mn 1.28.)
 STAGE 02 - 292 SQ.FT.



STAGE 01
STAGE 02

SIGNATURE OF APPLICANT

SIGNATURE OF ARCHITECT/ ENGINEER

PROJECT TITLE :		TYPE PLAN 02 (B - 02)		
DRAWING TITLE		ARCHITECTURAL DRAWING		
PREPARED BY :		NATIONAL BUILDING RESEARCH ORGANISATION HUMAN SETTLEMENTS PLANNING AND TRAINING DIVISION		
SCALE		8 FEET TO AN INCH		
DRAWN	MSN	CHECKED	APPROVED	
DATE	14.10.2016	DRAWING NO.: NBRO/ARANAYAKA/AD/02/001 (B-02)		

